Audit Trail: Case 18: Traffic control around a work area near an intersection, one lane closed

Field	Value
Plan status	0 changes · 2 needs attention · 10 checked · 3 pending · reference
MUTCD typical application	TA-21
CDOT standard sheet	S-630-1
Case	Case 18: Traffic control around a work area near an intersection, one lane closed
Taper length	245 ft (L (full merging taper))
Buffer space	250 ft
Device spacing: taper	35 ft
Device spacing: tangent	70 ft
Crew steps	16

Taper Length

Speed 35 mph < 45 mph threshold -> using L = W x S^2 / 60

L = 12 x 35^2 / 60 = 245 ft

Required: L = 245 ft (full taper for lane closure)

Field	Value
Closure type	lane
Offset (lane width)	12 ft
Required taper (L (full merging taper))	245 ft

Source: MUTCD 11th Ed. Sec 6B.08, Table 6B-4 (taper length L). Lane closures use the full merging taper length L (Table 6B-3).

CDOT reference: CDOT S-630-1 Case 18 (traffic control around a work area near an intersection, one lane closed; Sheet 10)

Buffer Space

MUTCD Table 6B-2: 250 ft (CDOT supplement silent at this speed)

Source: MUTCD 11th Ed. Sec 6B.06, Table 6B-2 (stopping sight distance)

Channelizing Device Spacing

35 mph -> 35 ft spacing (MUTCD Sec 6K.01: spacing equals speed in feet)

35 mph -> 70 ft spacing (MUTCD Sec 6K.01: spacing equals 2x speed in feet)

L = 245 ft / 35 ft max spacing -> 8 drums at 35.0 ft intervals

500 ft / 70 ft max spacing -> 9 cones at 62.5 ft intervals

Downstream taper: 50 ft at ~25 ft spacing -> 2 cones (MUTCD Sec 6B.08: 50-100 ft downstream taper); 9 tangent + 2 downstream = 11 cones total

Source: MUTCD 11th Ed. Sec 6K.01

Advance Warning Signs

Speed 35 mph, road_type = 'urban_low' -> Table 6B-1 category: urban_low

A = 100 ft, B = 100 ft, C = 100 ft

Position	Code	Station (ft)	Distance from Taper (ft)
C (furthest)	W20-1	1,295	300 upstream
1/2 C inside the outermost sign (Case 18)	R2-10	1,245	250 upstream
B (middle)	W20-5R	1,195	200 upstream
A (nearest)	W4-2R	1,095	100 upstream

Source: MUTCD 11th Ed. Table 6B-1

Colorado Requirements (CDOT S-630-1)

Check	Result	Citation	Detail
Signs on both sides of divided highway	PASS	CDOT S-630-1 (July 2026) Sheet 2, General Note 8	Required: True. Signs placed: 8 left, 8 right.
G20-5P Work Zone signs every 2,640 ft	PASS	CDOT S-630-1 (July 2026) Sheet 2, General Note 4	Zone length: 1,295 ft. Required: 1. Placed: 1.
Speed reduction <= 15 mph per sign installation	PASS	CDOT S-630-1 (July 2026) Sheet 2, General Note 3	No work-zone speed reduction. Posted speed 35 mph applies throughout the zone.
Flagger station lighting 500W @ 8 ft	PASS	CDOT S-630-1 (July 2026) Sheet 2, General Note 22	Not applicable (no flaggers).

AADT threshold for mobile operations (<= 2,000): Not applicable (not a mobile operation). (CDOT S-630-1 (July 2026) Sheet 23, Case 38 Note 1)

All Colorado checks pass: True

CDOT Case Reference

Case 18: Traffic control around a work area near an intersection, one lane closed

This scenario follows CDOT Standard Plan S-630-1, Case 18 (Sheet 10), "traffic control around a work area near an intersection, one lane closed", applied to one carriageway of a divided highway with every mainline warning and regulatory sign posted on both sides of the roadway, the median side included, per CDOT S-630-1 Sheet 2 General Note 8, plus a cross-street advance-warning set on each approach leg per MUTCD §6N.12 and the Sheet 10 advance-signing key.

Three disclosed departures from the plate: (1) the Case 18 plate typifies corner-quadrant work with a full cross-street closure train; this plan confines the work space to the mainline and places cross-street advance signing only. Corner-quadrant support is tracked at https://github.com/rtmakatura/conestruct/issues/128. (2) The opposing direction is the divided highway's other carriageway, a separate roadway this plan does not sign; the plate's opposing-direction signing does not apply. (3) The plate typifies rural sign placement; urban applications require block-based placement

per Sheet 10 Note 1. The plate's Type III corner barricade (work lasting more than 3 days) encloses the corner work area and is not placed, per departure (1).

Reference:
https://www.codot.gov/safety/traffic-safety/assets/s-standard-plans/s-630-1/S-630-01%20(19-Page%20Set).pdf

Geometry Validation

Work zone 500 ft vs required taper 245 ft (L (full merging taper)) + buffer 250 ft.

All geometry checks pass: True

Source: MUTCD 11th Ed. Sec 6B.06 (buffer) and Sec 6B.08 (taper)

Corridor Validation

OpenStreetMap corridor check produced warnings:

- No motorway/trunk/primary/secondary road detected at anchor (39.70900, -104.94070) within 50 m. Verify coordinates correspond to the actual work zone.

Cross-Street Approaches

Intersection on the near side of the work zone (centerline crossing at mainline station -200 ft).

Each cross-street leg receives its own advance set (W20-1, R2-10, R2-11), computed from that leg's own speed and road type; stations are measured along the leg from the intersection curb line, increasing away from the intersection.

Approach 'cross_a': 25 mph, urban_low, SIGNALIZED (signal operation review required). Sheet 10 advance-signing key: A = 100 ft at 25 mph (urban_low).

Code	Station (ft from curb line)	Placement rule
W20-1	200	2 x A = 200 ft, approach side
R2-10	100	A = 100 ft, approach side
R2-11	100	100 ft, departure side (Case 18)

Approach 'cross_b': 25 mph, urban_low, SIGNALIZED (signal operation review required). Sheet 10 advance-signing key: A = 100 ft at 25 mph (urban_low).

Code	Station (ft from curb line)	Placement rule
W20-1	200	2 x A = 200 ft, approach side
R2-10	100	A = 100 ft, approach side
R2-11	100	100 ft, departure side (Case 18)

Source: MUTCD §6N.12; CDOT S-630-1 Sheet 10, Cases 18/19 (advance-signing key)

Flagger Control

Not applicable for this scenario.

Source: MUTCD 11th Ed. Chapter 6D (Flagger Control) and Chapter 6E (One-Lane, Two-Way Traffic Control).

Pending Verification

3 reference(s) pending verification. On one carriageway of a divided highway the plan builds an 8 ft shoulder and fits lanes under a 52 ft half-road less that shoulder. Both values are CHOSEN: no MUTCD, S-630-1, Colorado Supplement

or Denver text found sets them. Verify against the site (#308). Tracking: https://github.com/rtmakatura/conestruct/issues/308

- [one_way_street_widths_chosen] On one carriageway of a divided highway the plan builds an 8 ft shoulder and fits lanes under a 52 ft half-road less that shoulder. Both values are CHOSEN: no MUTCD, S-630-1, Colorado Supplement or Denver text found sets them. Verify against the site (#308). (https://github.com/rtmakatura/conestruct/issues/308)
- [median_opening_unverified] Divided highway: the cross street crosses the median at an opening the CDOT S-630-1 Sheet 10 plates (Cases 18/19) don't draw. Confirm the signing at the median opening, and any turning traffic there, with the Engineer (S-630-1 Sheet 2 General Note 8: 'as directed by the Engineer'). Nothing is drawn for it (#312). (https://github.com/rtmakatura/conestruct/issues/312)
- [signal_operation_review_required] Signalized approaches (cross_a, cross_b): Conestruct places cross-street advance signing only and does not evaluate traffic-signal operation. The signal-operation review remains with the traffic control supervisor and the operating agency: phasing, timing, and signal-head visibility per MUTCD §6N.12 (items 04 and 05; 11th Ed. p. 848) and MUTCD Part 4. (https://github.com/rtmakatura/conestruct/issues/117)