Item #	Device Type	Description	CDOT Pay Item #	Unit	Quantity	Notes
1	SIGN_GENERIC	G20-1 ROAD CONSTRUCTION (NEXT 1000 FT)	630-80344	EACH	2	Unit is EACH for V1; CDOT Spec 630 bills by SF. Convert when sign sizes are known.
2	SIGN_GENERIC	G20-2 END ROAD WORK	630-80344	EACH	2	Unit is EACH for V1; CDOT Spec 630 bills by SF. Convert when sign sizes are known.
3	SIGN_GENERIC	G20-5P CONSTRUCTION ZONE plaque	630-80344	EACH	2	Unit is EACH for V1; CDOT Spec 630 bills by SF. Convert when sign sizes are known.
4	SIGN_GENERIC	R9-9 SIDEWALK CLOSED	630-80344	EACH	2	Unit is EACH for V1; CDOT Spec 630 bills by SF. Convert when sign sizes are known.
5	SIGN_GENERIC	W20-1 ROAD WORK AHEAD	630-80344	EACH	2	Unit is EACH for V1; CDOT Spec 630 bills by SF. Convert when sign sizes are known.
6	SIGN_GENERIC	W20-2 ROAD WORK 200 FT	630-80344	EACH	2	Unit is EACH for V1; CDOT Spec 630 bills by SF. Convert when sign sizes are known.
7	SIGN_GENERIC	W21-5aR RIGHT SHOULDER CLOSED AHEAD	630-80344	EACH	2	Unit is EACH for V1; CDOT Spec 630 bills by SF. Convert when sign sizes are known.
8	DRUM	36-inch channelizing drum with alternating oran	630-80360	EACH	3	
9	CONE	Traffic Cone (28-inch)	630-80380	EACH	23	
10	BARRICADE_TYPE_III	Type III barricade: three horizontal striped rails,	630-80332	EACH	2	
11	ARROW_BOARD	Trailer-mounted flashing arrow board (Type A, B	630-80358	EACH	1	